



FINAL REPORT **FEBRUARY 1991** 

REPORT NO. EVT 23-90

TRANSPORTABILITY TESTING OF CNU-309/E AND/OR CNU-322/E CONTAINERS IN A SIDE OPENING COMMERCIAL CONTAINER

Prepared for:

U.S. Army Defense Ammunition Center

and School

ATTN: SMCAC-DET Savanna, IL 61074-9639 Distribution Unlimited

92

92-13679

**VALIDATION ENGINEERING DIVISION SAVANNA, ILLINOIS 61074-9639** 



# **AVAILABILITY NOTICE**

A copy of this report will be furnished each attendee on automatic distribution. Additional copies or authority for reprinting may be obtained by written request from Director, U.S. Army Defense Ammunition Center and School, ATTN: SMCAC-DEV, Savanna, IL 61074-9639.

# **DISTRIBUTION INSTRUCTIONS**

Destroy this report when no longer needed. Do not return.

\*\*\*

Citation of trade names in this report does not constitute an official endorsement.

\*\*\*

The information contained herein will not be used for advertising purposes.

# UNCLASSIFIED SECURITY CLASSIFICATION OF THIS PAGE

REPORT DOCUMENTATION PAGE					Form Approved OMB No. 0704-0188	
12. REPORT SECURITY CLASSIFICATION UNCLASSIFIED			1b. RESTRICTIV	E MARKINGS	,	
2a. SECURITY CLASSIFICATION AUTHORITY		3. DISTRIBUTION / AVAILABILITY OF REPORT				
2b. DECLASSIFICATION / DOWNGRA	DING SCHEDULE		UNL	MITED		
4. PERFORMING ORGANIZATION RE	PORT NUMBER(S)		5. MONITORING	ORGANIZATION REI	PORT NUI	MBER(S)
EVT 23-90  8a. NAME OF PERFORMING ORGANIZATION   8b. OFFICE SYMBOL			7a. NAME OF MO	ONITORING ORGANI	ZATION	
U.S. Army Defense Am Center and School		(if applicable) SMCAC-DEV				
6c. ADDRESS (City, State, and ZIP Coo ATTN: SMCAC-DEV			7b. ADDRESS (C	City, State, and ZIP Co.	de)	
Savanna, IL 61074-963  Ba. NAME OF FUNDING / SPONSORIN ORGANIZATION		8b. OFFICE SYMBOL (if applicable)	9. PROCUREME	NT INSTRUMENT IDE	ENTIFICAT	TION NUMBER
U.S. Army Defense Am Center and School	munition	SMCAC-DET				
8c. ADDRESS (City, State, and Z	ie)	<del></del>	10. SOURCE OF	FUNDING NUMBERS	3	
ATTN: SMCAC-DET Savanna, IL 61074-963	19		PROGRAM ELEMENT NO.	PROJECT NO.	TASK NO	WORK UNIT ACCESSION NO.
11. TITLE (Include Security Classification) Transportability Testing of CNU-309/E and/or CNU-332/E Containers in a				······································		
Side Opening Commerc	ial Container					
12. PERSONAL AUTHOR(S)					_	
A. C. McIntosh						
13a. TYPE OF REPORT Final	13b. TIME COVER			PORT <i>(Year, Month, I</i> February	Day)	15. PAGE COUNT
16. SUPPLEMENTARY NOTATION	FROM	то	1 1771	10014419		
16. SUPPLEMENTANT NOTATION					·	
17. COSATI CODES		18. SUBJECT TERMS	(Continue on revers	no if nanoecony and ide	nih hy hi	not number
FIELD GROUP	SUB-GROUP	10. SOBJECT TERMS	(COMMING ON 161613	w ii necessaay aana iqe	nuly by bic	on number
		1				
19. ABSTRACT (Continue on reverse if		atife the block asserback			<del></del>	
The U.S. Army De	-		School (IIS A	DACS) Valid	ation E	naineerina
Division (SMCAC-DE)			-	• •		•
(SMCAC-DET), to test		•		_	•	
	_	- L	-	•		
ammunition in CNU-30				•		
into a side opening com		_	•			<del>-</del>
Transportability tests in	· ·	• •	•	•		•
simulation tests. After t		• `	•	•	_	
evolved. The U.S. Army Materiel Command (AMC) Drawing No. 19-48-7115 was found to be acceptable						
for the tested modes of transportation. The results of the tests are included in this report.						
OA DIOTRIBUTION LANGE AND THE CO.	- ADOTO 40-		04 45075455	SOURCE AL COST		
20. DISTRIBUTION / AVAILABILITY OF		<b></b>		BECURITY CLASSIFIC ASSIFIED	GATION	
22a. NAME OF RESPONSIBLE INDIVI JEROME H. KROHN	SAME AS RPT.	DTIC USERS	·	E (Include Area Code,	)	220. OFFICE SYMBOL SMCAC-DEV
Provious actions are chapter				SWICAC-DE V		

DD Form 1473, Jun 86

SECURITY CLASSIFICATION OF THIS PAGE UNCLASSIFIED

# U.S. ARMY DEFENSE AMMUNITION CENTER AND SCHOOL VALIDATION ENGINEERING DIVISION SAVANNA, IL 61074-9639

# REPORT NO. EVT 23-90 TRANSPORTABILITY TESTING OF, CNU-309/E AND/OR CNU-332/E CONTAINERS IN A SIDE OPENING COMMERCIAL CONTAINER

Junear Land Long				
<b>₽</b> y				
Distribution/				
Ava	lability Codes			
	Avail and/or			
Dist	Special			
1. 6				
17-1				

# **TABLE OF CONTENTS**

PART	GE NO.
1. INTRODUCTION	1-1
A. BACKGROUND	1-1
B. AUTHORITY	1-1
C. OBJECTIVE	1-1
D. CONCLUSIONS	1-1
E. RECOMMENDATIONS	1-2
2. ATTENDEES	2-1
3. TEST PROCEDURES	3-1
4. TEST SPECIMEN & RESULTS	4-1
A. RAIL IMPACT	4-1
B. ROAD TEST	4-4
C. SHIPBOARD TRANSPORTATION SIMULATION TEST	4-3
5. LOADING AND BRACING PROCEDURE	5-1
6. PHOTOGRAPHS	6-1

#### INTRODUCTION

- A. BACKGROUND. The U.S. Army Defense Ammunition Center and School (USADACS), Validation Engineering Division (SMCAC-DEV), was requested by USADACS, Transportation Engineering Division (SMCAC-DET), to test a loading and bracing procedure in a side opening commercial container of 30mm ammunition in CNU-309/E or CNU-332/E containers. A total of 24 inertly-filled containers were loaded. into a side opening commercial container. The gross weight of the loaded container was 33,350 pounds. Transportability tests were carried out in agreement with the procedures in part 3.
- B. <u>AUTHORITY</u>. These tests were conducted in agreement with mission responsibilities delegated by U.S. Army Armament, Munitions and Chemical Command (AMCCOM), Rock Island, IL. Reference is made to Change 4, 4 October 1974; to AR-740-1, 23 April 1971; Storage and Supply Operations; and AMCCOM-R 10-17, 13 January 1986; Mission and Major Functions of USADACS.
- C. <u>OBJECTIVE</u>. The objective of these tests was to determine if the proposed loading and bracing procedure in side opening commercial containers of 30mm ammunition loaded in CNU-309/E or CNU-322/E containers will satisfy road, rail, and ship transportation environments
- D. <u>CONCLUSIONS</u>. The proposed loading and bracing with wooden dunnage in side opening commercial containers of 30mm ammunition loaded in CNU-309/E or CNU-322/E containers passed the rail transportation, road hazard, road, washboard, and shipboard transportation simulation tests.

E. RECOMMENDATIONS. It is recommended that the loading procedure for 30mm ammunition in CNU-309/E or CNU-322/E containers transported in a side opening commercial container be accepted.

# TRANSPORTABILITY TESTING OF CNU-309/E AND/OR CNU-332/E CONTAINERS IN A SIDE OPENING COMMERCIAL CONTAINER

# **AUGUST 1990**

# **TEST ATTENDEES**

NAME AND PHONE NUMBER	ORGANIZATION
A.C. McIntosh Test Engineer DSN 585-8989 815-273-8989	U.S. Army Defense Ammunition Center and School ATTN: SMCAC-DEV Savanna, IL 61074-9639
Quinn D. Hartman General Engineer DSN 585-8992 815-273-8992	U.S. Army Defense Ammunition Center and School ATTN: SMCAC-DEV Savanna, IL 61074-9639
David V. Valant Electronics Technician DSN 585-8988 815-273-8999	U.S. Army Defense Ammunition Center and School ATTN: SMCAC-DEV Savanna, IL 61074-9639
Steven L. Von Thun Engineering Draftsman DSN 585-8093 815-273-8093	<ul><li>U.S. Army Defense Ammunition Center and School</li><li>ATTN: SMCAC-DEV</li><li>Savanna, IL 61074-9639</li></ul>
William R. Frerichs Chief, Transportation Division DSN 585-8071 815-273-8071	<ul><li>U.S. Army Defense Ammunition Center and School</li><li>ATTN: SMCAC-DET</li><li>Savanna, IL 61074-9639</li></ul>
Richard S. Haynes Engineering Technician DSN 585-8225 815-273-8096	U.S. Army Defense Ammunition Center and School ATTN: SMCAC-DET Savanna, IL 61074-9639

Dan Healy Senior Inspector 708-392-6846 202-828-1999 Association of American Railroads/ Bureau of Exlposives 309 N. Douglas Arlington Heights, IL 60004

#### TEST PROCEDURES

- A. RAIL IMPACT TEST. The side opening commercial container, with the inert load of 30mm containers, was positioned on a container chassis and securely locked in place using the twist locks at each corner. The chassis, with the mounted container, was secured to a Trailer-on-flatcar (TOFC) equipped with friction draft gear. Equipment needed to do the test included the specimen (hammer) car, five empty railroad cars to serve as the anvil (total weight of the railroad cars was 250,000 pounds), and a railroad locomotive. The anvil cars were positioned on a level section of track with the draft gear compressed, with air and hand brakes set. The locomotive unit pulled the specimen car several hundred yards away from the anvil cars, and, then, pushed the specimen car toward the anvil at a predetermined speed, disconnected from the specimen car (approximately 50 yards away from the anvil cars), which allowed the specimen car to roll freely along the track until it struck the anvil. This constituted an impact. Impacting was accomplished at speeds of 4, 6, and 8 mph in one direction, and at a speed of 8 mph in the opposite direction. The 4 and 6 mph impact speeds were approximate; the 8 mph speed was a minimum. Impact speeds were determined by using an electronic counter to measure the time required for the specimen car to traverse an 11-foot distance immediately before contact with the anvil cars.
- B. <u>ROAD HAZARD COURSE</u>. The side opening commercial container, with the inert load of 30mm ammunition containers, was positioned on a container chassis and securely locked in place using the twist locks at each corner. The chassis was towed over the road hazard course with a tractor two times at a speed of approximately 5 mph. The speed was increased or decreased, as appropriate, to produce the most violent load response.

- C. ROAD TRIP TEST. Using a suitable tractor, the side opening commercial container, with the inert load of 30mm ammunition containers, was towed for a total distance of at least 30 miles over a combination of roads surfaced with gravel, concrete, and asphalt. The test route included curves, corners, railroad crossings, cattle guards, stops, and starts. This test vehicle traveled at the maximum speed suitable for the particular road traversed, except as limited by legal restrictions. The road test usually concludes with three full airbrake stops while traveling in the forward direction and one in the reverse direction while traveling down a 7 degree grade. During this test the panic stops were omitted due to the fact the test specimen sustained larger shock forces in the rail impact test, than would be realized in a panic stop.
- D. <u>POST ROAD TRIP HAZARD COURSE</u>. After completion of the road trip test, the chassis was towed over the road hazard course with a tractor two times at a speed of approximately 5 mph. The speed was increased or decreased, as appropriate, to produce the most violent load response.
- E. <u>WASHBOARD COURSE</u>. The side opening commercial container, with an inert load of 30mm ammunition containers, was towed over the washboard course at a speed which produced the most violent response in the particular test load (as indicated by the resonant frequency of the suspension system beneath the load).
- F. <u>SHIPBOARD TRANSPORTATION SIMULATION</u>. The side opening commercial container, with the inert load of 30mm ammunition containers, was positioned onto the Shipboard Transportation Simulator (STS) and securely locked into place using the cam lock at each corner. The STS began oscillation at an amplitude of 30 degrees +/- 2 degrees, either side, at a frequency of 2 cycles-per-minute (30 seconds +/- 2 seconds total per roll period). This frequency was maintained for at least 15 minutes during which time the load was observed for apparent defects which could cause a safety hazard. The frequency of oscillation was then

increased to 4 cycles-per-minute (15 seconds +/- 1 second roll period) and was maintained for two hours. When an inspection of the load did not show an impending failure, the frequency of oscillation was increased to 5 cycles-per-minute (12 seconds +/- 1 second cycle time), and the equipment was operated for four more hours. This operation does not necessarily have to be continuous; however, no change or adjustments to the load or load restraints shall be permitted at any time during the test. The test load (specimen) shall not be removed from the apparatus, after once positioned in place, until the test is completed or stopped.

# TEST RESULTS

#### TEST NO 1

A. RAIL IMPACT TEST

DATE: 21 June 1990

TEST SPECIMEN: TRANSPORTABILITY TESTING OF CNU-309/E AND/OR
CNU-332/E CONTAINERS IN A SIDE OPENING
COMMERCIAL CONTAINER

TEST TOFC NO.: TTX 151044

LT.WT.: 73,400 pounds

CHASSIS NO.: 5394

WT.: 6,10C pounds

SIDE OPENING MILVAN:USAF 0014335

WT.: 6,050 pounds

LADING & DUNNAGE (27,885 + 415)

WT.: 28,300 pounds

TOTAL SPECIMEN WT.: 113,850 pounds

BUFFER CAR (5 CARS) WT.: 250,000 pounds

IMPACT NO. END STRUCK VELOCITY REMARKS

1 Forward 4.36 Test failed after first

impact. Permanent deformation to the side opening container

end wall.

# TEST RESULTS

#### TEST NO. 2

#### A. RAIL IMPACT TEST

DATE: 19 September 1990

TEST SPECIMEN: TRANSPORTABILITY TESTING OF CNU-309/E AND/OR
CNU-332/E CONTAINERS IN A SIDE OPENING
COMMERCIAL CONTAINER

TEST TOFC NO.: TTX 601760 LT.WT.: 67,600 pounds

CHASSIS NO.: 5394 WT.: 6,100 pounds

SIDE OPENING MILVAN:USAF 0014335 WT.: 6,050 pounds

LADING & DUNNAGE (27,885 + 663) WT.: 28,548 pounds

TOTAL SPECIMEN WT.: 108,298 pounds

BUFFER CAR (5 CARS) WT.: 250,000 pounds

IMPACT NO.	END STRUCK	VELOCITY	REMARKS
1	Forward	4.46	No movement of side opening container walls.
2	Forward	4.51	No movement of side opening container walls.
3	Forward	6.53	Permanent deformation to rear container wall. Test stopped.

# **TEST RESULTS**

#### TEST NO. 3

#### A. RAIL IMPACT TEST

DATE: 6 November 1990

TEST SPECIMEN: TRANSPORTABILITY TESTING OF CNU-309/E AND/OR CNU-332/E CONTAINERS IN A SIDE OPENING COMMERCIAL CONTAINER

TEST TOFC NO.: TTX 250594 LT.WT.: 74,900 pounds

CHASSIS NO.: 4268 WT.: 6,100 pounds

SIDE OPENING MILVAN:USAF 0014398 WT.: 6,050 pounds

LADING & DUNNAGE (27,885 + 682) WT.: 28,882 pounds

TOTAL SPECIMEN WT.: 115,617 pounds

BUFFER CAR (5 CARS) WT.: 250,000 pounds

IMPACT NO.	END STRUCK	VELOCITY	REMARKS
1	Forward	4.36	No movement of side opening container walls.
2	Forward	6.57	No movement of side opening container walls.
3	Forward	8.24	No movement of side opening container end walls.
4	Reverse	8.31	No damage to container or ammunition containers.

#### **ROAD TEST DATA**

<b>TEST</b>	NO.	4
11:01	110.	7

DATE 7 November 1990

TRANSPORTABILITY TESTING OF CNU-309/E AND/OR CNU-332/E CONTAINERS IN A SIDE OPENING COMMERCIAL CONTAINER

PASS 1-A OVER FIRST SERIES OF TIES .11 MIN 5.16 MPH
PASS 1-B OVER SECOND SERIES OF TIES .10 MIN 5.68 MPH

REMARKS: No damage to side opening container or movement of 30mm load.

PASS 2-A OVER FIRST SERIES OF TIES .10 MIN 5.68 MPH
PASS 2-B OVER SECOND SERIES OF TIES .09 MIN 6.31 MPH

REMARKS: No damage to side opening container or movement of 30mm load.

30 MILE ROAD TRIP: No damage to container or 30mm load.

PASS 3-A OVER FIRST SERIES OF TIES .09 MIN 6.31 MPH
PASS 3-B OVER SECOND SERIES OF TIES .10 MIN 5.68 MPH

REMARKS: No damage to side opening container or movement of 30mm load.

PASS 4-A OVER FIRST SERIES OF TIES .10 MIN 5.68 MPH
PASS 4-B OVER SECOND SERIES OF TIES .09 MIN 6.31 MPH

REMARKS: No damage to side opening container or movement of 30mm load.

WASHBOARD COURSE: Loads and container remained intact.

STS: Load and container remained intact.

# LOADING AND BRACING PROCEDURES

APPROVED BY			
BUREAU	BUREAU OF EXPLOSIVES		
Ì			
04TE	_		

LOADING AND BRACING WITH WOODEN DUNNAGE IN SIDE OPENING COMMERCIAL CONTAINERS OF GAU-8/A 30MM AMMUNITION PACKAGED IN AUTOMATIC LOADING SYSTEM (ALS) CNU-309/E AND/OR CNU-332/E CONTAINERS

DOADING AND BRACING SPECIFICATIONS SET FORTH WITHIN THIS DRAWING ARE APPLICABLE TO LOADS THAT ARE TO BE SHIPPED BY TRAILER/CONTAINER-ON-FLAT-CAR (TICOFC) RAIL CARRIER SERVICE. THESE SPECIFICATIONS MAY ALSO BE USED FOR LOADS THAT ARE TO BE MOVED BY MOTOR OR WATER CARRIERS. SEE GENERAL NOTE "M" ON PAGE 2.

	REVIS	SIONS	6	1 -	SI'S RS	
T		ļ		- w	Seenada 4	valuet
1	-		-		jist, ventuni	
	-		1			
İ			-	-		
I -					Market Light Clinida	MB \$0-00k
 			US. A	RMY MA	TERIEL C	COMMAND
	-					
	-		aves	DIVISION	DRAWNIE	PLE
			19	48	7115	SP
	-		'•	"		15M6

DO NOT SCALE

#### GENERAL NOTES

- THIS DOCUMENT HAS BEEN PREPARED AND ISSUED IN ACCORDANCE WITH AR 740-1 AND AUGMENTS TM 743-200-1 (CHAPTER 5).
- B. THE SPECIFED OUTLOADING PROCEDURES ARE APPLICABLE TO GAU-S/A
  30MM AMMUNITION IN AUXOMATIC LOADING SYSTEM (ALS), CNU-309/E
  AND/OR CNU-322/E CONTAINERS, THE SHIPPING AND STORAGE CONFIGURATION FOR THE CONTAINERS CONSISTS OF TWO CONTAINERS
  UNITIZED INTO ONE TWIN-PACK UNIT. SUBSEQUENT REFREINCE TO
  TWIN-PACK UNIT HERIN MEANS TWO CNU-309/E OR CNU-332/E CONTAINERS
  WITH 30MM AMMUNITION UNITIZED TOGETHER. SEE PAGE 3 FOR DETAILS
  OF THE TWIN-PACK UNITS. CAUTION: REGARDLESS OF THE QUANTITY OF
  TWIN-PACK UNITS TO BE SHIPPED, THE "MAXIMUM GROSS WEIGHT" OF THE
  CONTAINER MUST NOT BE EXCEEDED.
- C. THE LOAD AS SHOWN IS BASED ON A 6,050 POUND 20' LONG BY 8' WIDE BY 8'-6" HIGH SIDE OPENING INTERMODAL COMMERCIAL CONTAINER WITH INSIDE DIMENSIONS OF 19'-4" LONG BY 89" WIDE BY 88" HIGH. THE LOAD IS DESIGNED FOR TRAILER/CONTAINER-ON-FLAT-CAR (T/COFC) SHIPMENT, HOWEVER, THE LOAD AS DESIGNED CAN ALSO BE MOVED BY OTHER SURFACE MODES OF TRANSPORT, NOTICE: OTHER CONTAINERS OF THE SAME DESIGN CONFIGURATION CAN BE USED.
- D. WHEN LOADING CNU-309/E OR CNU-332/E TWIN PACK UNITS, THEY ARE TO BE POSITIONED SO AS TO ACHEVE A TIGHT LOAD (TIGHT AGAINST THE END AND SIDE DUNNAGE ASSEMBLES), ALTHOUGH A TOTAL OF 1-1/2" OF UNBLOCKED SPACE ACKNOSS THE WIDTH OF A LOAD BAY IS PERMITTED, LATERAL VOIDS WITHIN THE LOAD ARE TO BE HELD TO A MINIMUM, EXCESSIVE SLACK CAN BE ELIMINATED FROM A LOAD BY LAMINATING ADDITIONAL PIECES OF APPROPRIATE THICKNESS TO THE BEARING PECE ON THE SIDE FILL ASSEMBLY, NAIL EACH ADDITIONAL PIECE TO THE BEARING PECE W/I APPROPRIATELY SIZED NAIL EVERY 12", ADDITIONALLY, THE THICKNESS OF THE BEARING PIECE MAY BE ADJUSTED AS REQUIRED TO FACILITATE VARIANCE IN THE CNU-309/E OR CNU-302/E TWIN-PACK UNIT SIZE.
- E. DUNNAGE LUMBER SPECIFED IS OF NOMINAL SIZE. FOR EXAMPLE, 1° X 4° MATERIAL IS ACTUALLY 3/4° THICK BY 3-1/2° WIDE AND 2° X 6° MATERIAL IS ACTUALLY 1-1/2° THICK BY 5-1/2° WIDE.
- F. A STAGGERED NAILING PATTERN WILL BE USED WHENEVER POSSIBLE WHEN NAILS ARE DRIVEN INTO JOINTS OF DUNINAGE ASSEMBLIES OR WHEN LAMINATING DUNINAGE. ADDITIONALLY, THE NAILING PATTERN FOR AN UPPER PIECE OF LAMINATED DUNINAGE WILL BE ADJUSTED AS REQUIRED SO THAT A NAIL FOR THAT PIECE WILL NOT BE DRIVEN THROUGH ONTO OR RIGHT BESIDE A NAIL IN A LOWER PIECE.
- G. CAUTION: DO NOT NAIL DUNNAGE MATERIAL TO THE CONTAINER WALLS OR FLOOR, ALL NAILING WILL SE WITHIN THE DUNNAGE.
- H. PORTIONS OF THE CONTAINER DEPICTED WITHIN THIS DRAWING, SUCH AS THE SIDE DOORS, HAVE NOT BEEN SHOWN IN THE LOAD VIEWS FOR CLARITY PURPOSES.
- J. THIS ITEM IS A DOT CLASS "A" EXPLOSIVE, THE OUTLOADING PROCEDURES SPECIFIED HEREIN CAN ALSO BE UTILIZED FOR THE SHIPMENT OF THE DEPICED TWIN-PACK UNITS WHICH THEY ARE LOADED WITH AN ITEM WHICH IS IDENTIFIED DIFFERENTLY BY NOMENCLATURE THAN THE ITEM DESIGNATED WITHIN THE DRAWING TITLE. SEE GENERAL NOTE "L" BELOW.
- K. WHEN REFERING TO THE TWIN-PACK UNIT LENGTH OR UNIT WIDTH THE 53" OR 52-3/8" DIMENSION OF THE TWIN-PACK UNIT CONSTITUTES THE LENGTH AND THE 28-3/4" DIMENSION CONSTITUTES THE WIDTH. SEE THE TWIN-PACK UNIT DETAILS ON PAGE 3.
- L. CNU-309/E AND CNU-332/E TWIN-PACK UNITS ARE CERTIFED PACKAGING APPROVED IN ACCORDANCE WITH TITLE 49 OF THE CODE OF FEDERAL REGULATIONS PARAGRAPH 173.7 (A) BY CONTAINER CERTIFICATION NUMBER AF-78-51 AND DOT EXEMPTION 8101. A COPY OF THE DOT-E8101 WILL BE PROVIDED THE CARRIER AT TIME OF LOADING FOR CARRIAGE ABOARD THE VEHICLE.

( CONTINUED AT RIGHT )

#### (GENERAL NOTES CONTINUED)


- M. REQUIREMENTS CITED WITHIN THE BUREAU OF EXPLOSIVES PAMPHLET &C. APPLY WHEN THE SHIPMENT MOVES BY TRAILER/CONTAINER-ON-FLAT-CAR (T/COFC). SPECIAL T/COFC NOTES FOLLOW:
  - 1. A LOADED CONTAINER MUST BE ON A CHASSIS EQUIPPED WITH TWO BOGIE ASSEMBLES WHEN BEING MOVED IN TOPC SERVICE.
  - THE LOAD LIMIT OF A T/COPC RAILCAR MUST NOT BE EXCEEDED, NOR WILL A CAR BE LOADED SO THAT THE TRUCK UNDER ONE END OF THE CAR CARRIES MORE THAN ONE-HALF OF THE LOAD LIMIT FOR THAT CAR.
- N. DURING INTRASTATE AND/OR INTERSTATE MOVES BY MOTOR CARRER, A PROPER CHASSIS OR MODIFIED FLAT BED TRAILER MUST BE USED TO PRECLUDE VIOLATION OF ONE OR MORE "WEIGHT LAWS" APPLICABLE TO THE STATE OR STATES INVOLVED.
- O. CONVERSION TO METRIC EQUIVALENTS: DIMENSIONS WITHIN THIS DOCUMENT ARE EXPRESSED IN INCRES AND WEIGHTS ARE EXPRESSED IN POUNDS. WHEN NECESSARY, THE METRIC EQUIVALENTS MAY BE COMPUTED ON THE BASIS OF ONE INCH EQUALS 23.4MM AND ONE POUND EQUALS 0.454KG.
- P. RECOMMENDED SEQUENTIAL LOADING PROCEDURES:
  - 1. PREFABRICATE TWO ENDWALL BUFFERS, TWO SIDEWALL BUFFERS, TWO SEPARATOR GATES, TWO CENTER GATES, AND TWO SIDE FILL ASSEMBLES.
  - 2. INSTALL ONE ENDWALL BUFFER AND ONE SIDEWALL BUFFER.
  - 3. LOAD THREE CHU-309/E OR CHU-332/E TWIN PACK UNITS.
  - 4. INSTALL ONE SEPARATOR GATE.
  - 5. REPEAT STEP 3.
  - 6. REPEAT STEP 2.
  - 7. REPEAT STEP 3.
  - 8. REPEAT STEP 4.
  - 9. REPEAT STEP 3.
  - 10. INSTALL TWO CENTER GATES AND SIX STRUTS.
  - 11. INSTALL TWO SIDE FILL ASSEMBLES
- Q. TWIN PACK UNITS OF CNU-309/E CONTAINERS SHOULD BE INSPECTED AND, AS REQUIRED, LOOSE UNITIZING STEEL STRAPPING MUST BE REPLACED OR RETENSIONED.

#### MATERIAL SPECIFICATIONS

: SE TM 743-200-1 (DUNNAGE LUMBER) AND FED SPEC MM-L-751.


NAILS ---- FED SPEC FF-N-108; COMMON.

PAGE 2



# TWIN-PACK UNIT (CNU-309/E CONTAINER)

- TWO (2) - 2,350 LES (APPROX) - 39.9 CUBIC FEET




# TWIN-PACK UNIT ( CNU-332/E CONTAINER )

TWIN PACK UNIT DATA:


-- TWO (2) --- 2,350 LBS (APPROX) -- 39,4 CUBIC FEET

TWIN-PACK UNIT DETAILS


PAGE 3



ISOMETRIC VIEW



- 3 SEPARATOR GATE (2 REQD), SEE THE DETAIL ON PAGE 5. SEE GENERAL NOTE "F" ON PAGE 2.
- 4 CENTER GATE ASSEMBLY (2 REQD), SEE THE DETAIL ON PAGE 6.
- STRUT, 2" X 6" BY CUT TO FIT (REF; 12-1/2") (6 REQD). TOENAIL TO PECE MARKED ( W/2-164 NAILS AT EACH END,
- 6) SIDE FILL ASSEMBLY (2 REQD), SEE THE DETAIL ON PAGE 6, SEE GENERAL NOTE TO ON PAGE 2.
- 7) FILL MATERIAL, 4" WIDE BY 42" LONG MATERIAL (AS REQD.). NAIL EACH PIECE TO THE VERTICAL PIECES OF THE SIDE FILL ASSEMBLY, PIECE MARKED (6), AND/OR LAMINATE TOGETHER W/4 NAILS OF A SUITABLE SIZE (64 NAILS FOR 1" MATERIAL AND '100 NAILS FOR 2" MATERIAL).



• •

SEPARATOR GATE


BILL OF MATERIAL			
LINEAR FEET	SOARD FEET		
21	7		
43	22		
40			
	40 57		
<del></del>	<del></del>		
NO, REQD	POUNDS		
72	1/2		
108	1-3/4		
24	3/4		
	LINEAR FEET  21 43 4 40 57  NO. REQD  72 108		

#### SPECIAL NOTES:

- 1. A 12 TWIN-PACKLOAD IS SHOWN IN A SIDE OPENING INTERMODAL COMMERCIAL CONTAINER.
- 2. THE CNU-332/E TWIN-PACK UNITS ARE SHOWN IN THE ISOMETRIC VEW ON PAGE 4. THE PROCEDURES ARE ALSO APPLICABLE FOR SHEMENTS OF CNU-309/E TWIN-PACK UNITS. SEE SPECIAL NOTES 3 AND 4.
- 8. THE SEPARATOR GATES, SHOWN AS PECCES MARKED (3), ARE ONLY REQUIRED WHEN SHIPPING THE CNU-332/E TWIN-PACK UNITS.
- 4. BOTH THE CNU-309/E TWIN-PACK UNITS AND THE CNU-322/E TWIN-PACK UNITS MAY BE SHIPPED IN THE SAME CONTAINER, HOWEVER, ALL UNITS WITHIN A LOAD BAY MUST BE OF THE SAME MODELL, A SPARATOR GAITE, PECE MARKED (3), IS REQUIRED BETWEEN ADJACENT LENGTHWISE LOAD UNITS OF UNLIKE MODELS.

#### LOAD AS SHOWN

IRM	CUANTITY	WEIGHT ( AP	MOX )
DUNNAGE -	UNIT12	415 LBS	
<del></del>	TOTAL WEIGHT	34,645 LBS (	(APPROX.)




---- TEST DRAWING ----NOT TO BE USED AS AN OUTLOADING/
UNITIZATION/STANDARD PROCEDURE

# FOR INFORMATION ONLY

S. VON THUN	30mm CONTAINERS IN	SIDE-OPENING	
A. MCINTOSH	CONTAINER (2nd TEST)		
CHIEF, VALIDATION ENGINEERING DIVISION  J, KROHN		SEPTEMBER 1990	

# 30mm CONTAINERS IN SIDE-DPENING CONTAINER



# FOR INFORMATION ONLY

TITLE

30nm CONTAINERS IN SIDE-OPENING CONTAINER (2nd TEST)

DWG NO

90-023-0-T00011

VALIDATION ENGINEERING DIVISION

SHEET 2 OF 8

# 30mm CONTAINERS IN SIDE-OPENING CONTAINER

# KEY NUMBERS

- ① BLOCKING ASSEMBLY (2 REQD). SEE DETAIL ON SHEET 4.
- 2 SIDEWALL BUFFER (2 REDD). SEE DETAIL ON SHEET 5.
- 3 SEPARATOR GATE (2 REQD). SEE DETAIL ON SHEET 6.
- (4) CENTER FILL ASSEMBLY (1 REDD). SEE DETAIL ON SHEET 7.
- (S) SIDE FILL ASSEMBLY (2 REQD). SEE DETAIL ON SHEET 8.
- (6) FILL MATERIAL, 4" WIDE X 42" LONG BY THICKNESS(ES) REQUIRED TO CONTACT THE DOORS WHEN THEY ARE CLOSED. LAMINATE TO THE VERTICAL PIECES OF THE SIDE FILL ASSEMBLY, PIECE MARKED (5).

# FOR INFORMATION ONLY


TITLE

30mm CONTAINERS IN SIDE-OPENING CONTAINER (2nd TEST) DWG NO

90-023-0-T00012

VALIDATION ENGINEERING DIVISION

SHEET 3 DF 8



BLOCKING ASSEMBLY

FOR INFORMATION ONLY

TITLE


30mm CONTAINERS IN SIDE-OPENINIG CONTAINER (2nd TEST)

DWG NO

90-023-0-T00013

VALIDATION ENGINEERING DIVISION

SHEET 4 OF 8



# FOR INFORMATION ONLY

TITLE


30mm CONTAINERS IN SIDE-OPENING CONTAINER (2nd TEST)

DWG NO

90-023-0-T00014

VALIDATION ENGINEERING DIVISION

SHEET 5 OF 8



SEPARATOR GATE

<u>FOR INFORMATION ONLY</u>

TITLE


30mm CONTAINERS IN SIDE-OPENING CONTAINER (2nd TEST)

OWG NO

90-023-0-T00015

VALIDATION ENGINEERING DIVISION

SHEET 6 OF 8



ENR INENRMATION ONLY

TITLE


30mm CONTAINERS IN SIDE-OPENINIG CONTAINER (2nd TEST)

DWG NO

90-023-0-T00016

VALIDATION ENGINEERING DIVISION

SHEET 7 OF 8



SIDE FILL ASSEMBLY

FOR INFORMATION ONLY

TITLE

30nm CONTAINERS IN SIDE-OPENINIG CONTAINER (2nd TEST)

DWG NO

90-023-0-T00017

VALIDATION ENGINEERING DIVISION


SHEET 8 OF 8

---- TEST DRAWING ----NOT TO BE USED AS AN OUTLOADING/
UNITIZATION/STANDARD PROCEDURE

# FOR INFORMATION ONLY

S. VON THUN	30mm CONTAINERS IN SIDE-OPENING
A. MCINTOSH	CONTAINER (3rd TEST)
CHIEF, VALIDATION ENGINEERING DIVISION  J. KROHN	90-023-0-T00018   DCTDBER 1990

# 30mm CONTAINERS IN SIDE-OPENING CONTAINER



# <u>FOR INFORMATION ONLY</u>

TITLE

30mm CONTAINERS IN SIDE-OPENING CONTAINER (2nd TEST) DWG NO

90-023-0-T00019

VALIDATION ENGINEERING DIVISION

SHEET 2 OF 4

# 30mm CONTAINERS IN SIDE-OPENING CONTAINER

# KEY NUMBERS

- (1) BLOCKING ASSEMBLY (2 REDD). SEE DETAIL ON SHEET 4.
- 2 SIDEWALL BUFFER (2 REQD). SEE DETAIL ON SHEET 5.
- 3 SEPARATOR GATE (2 REDD). SEE DETAIL ON SHEET 6.
- (4) CENTER FILL ASSEMBLY (1 REDD). SEE DETAIL ON SHEET 7.
- (5) SIDE FILL ASSEMBLY (2 REQD). SEE DETAIL ON SHEET 8.
- 6 FILL MATERIAL, 4" WIDE X 42" LONG BY THICKNESS(ES) REQUIRED TO CONTACT THE DOORS WHEN THEY ARE CLOSED. LAMINATE TO THE VERTICAL PIECES OF THE SIDE FILL ASSEMBLY, PIECE MARKED ⑤.
- 7 FILL MATERIAL, 2" X 4" X 7'-1/2" (2 REQD). PLACE LIFTING RING IN A DOWNWARD POSITION, THEN NAIL TO BUFFER PIECE OF BLOCKING ASSEMBLY, PIECE MARKED (1), W/4-10d NAILS.

# FOR INFORMATION ONLY


TITLE

30nm CONTAINERS IN SIDE-OPENING CONTAINER (3nd TEST) OMG NO

90-023-0-T00020

VALIDATION ENGINEERING DIVISION

SHEET 3 OF 4



FOR INFORMATION ONLY

TITLE

30mm CONTAINERS IN SIDE-OPENINIG CONTAINER (3rd TEST)


DMG NO

90-023-0-T00021

VALIDATION ENGINEERING DIVISION


SHEET 4 OF 4

# **PHOTOGRAPHS**



U.S. ARMY DEFENSE AMMUNITION CENTER AND SCHOOL - SAVANNA, IL

Photo No. AO317-SPN-90-289-5180 This photo shows the center gate used to maintain a fixed distance between 30mm ammunition containers. Note, broken load bearing pieces on the top and bottom of the assembly.



side opening commercial container after being subjected to a rail impact test. Note, load standoff from left side and end wall deformation on the right side of the container. A single plywood sheet was used on each end wall butter Photo No. AO317-SPN-90-289-5185 This photo shows the 30mm inert-filled ammunition containers loaded in a



Photo No. AO317-SPN-90-289-5181. This photo shows the 30mm ammunition containers and a single sheet end wall buffer. Note, deformation of the end wall. The deformation resulted in a 3-inch offset from the opposite end wall of the load.



Photo No. AO317-SPN-90-289-5183 This photo shows the standoff off displacement of the load after a rail impact. Normally, the load must remain within one inch of the end wall. The offset is approximately three inches.




Photo No. AO317-SPN-90-289-5182 This photo shows the standoff off displacement of the load after a rail impact. Normally, the load must remain within one inch of the end wall. The offset is approximately three inches.



Photo No. AO317-SPN-90-289-5191 This is a profile of a side opening commercial container after a rail impact. U.S. ARMY DEFENSE AMMUNITION CENTER AND SCHOOL - SAVANNA, IL

Note, end wall deformation.

6-7






Photo No. AO317-SPN-90-289-5190 This is a profile of a side opening commercial container after a rail impact. Note, end wall deformation.



U.S. ARMY DEFENSE AMMUNITION CENTER AND SCHOOL - SAVANNA, IL

Photo No. AO317-SPN-90-289-5195 This photo shows the test loads after a rail impact. The rear container has been opened for inspection of the load. This container is loaded with 30mm ammunition containers.



chassis and secured to a Trailer-on-flatcar (TOFC). This is a common rail shipment configuration used for the rail Photo No. AO317-SPN-90-289-5196. This photo shows two side opening commercial containers, mounted on a impact test.